

BISMILLAH CONSTRUCTION

Bill of Quantities / Client Quotation

Generated: 31 Jul 2026, 2:30 pm

Period: All Time / Current Snapshot

Project: BOQ Complex Villa - 1785488400681 | Revision: Version 2 (ACTIVE)

REVISION Version 2	STATUS ACTIVE	GRAND TOTAL Rs. 12,77,000
-----------------------	------------------	------------------------------

SECTION 1: SUBSTRUCTURE CIVIL WORK					Group: Civil
1.1 EXCAVATION & EARTHWORK					
Description / Specification	Mode	Est. Qty	Unit	Rate (₹)	Amount (₹)
Machine excavation in hard soil	Calculated	200	Cu.m	600.00	1,20,000.00
Backfilling and leveling lump sum	Lump Sum	-	-	-	25,000.00
1.2 PCC & RCC FOUNDATION					
Description / Specification	Mode	Est. Qty	Unit	Rate (₹)	Amount (₹)
PCC bed 100mm thick	Calculated	150	Sq.m	400.00	60,000.00
RCC M25 grade in footings	Calculated	80	Cu.m	6,000.00	4,80,000.00
OPC Cement for plastering Material Link: Test OPC Cement Bag 1785488400696	Calculated	100	Bag	400.00	40,000.00
TOTAL FOR SECTION: SUBSTRUCTURE CIVIL WORK					Rs. 7,25,000.00

SECTION 2: INTERIOR FINISHING PACKAGE					Group: Finishing & Services
2.1 VITRIFIED & GRANITE FLOORING					
Description / Specification	Mode	Est. Qty	Unit	Rate (₹)	Amount (₹)
800x800 vitrified floor tile installation	Calculated	1,200	Sq.ft	180.00	2,16,000.00
Kitchen granite counter slab moulding	Lump Sum	-	-	-	45,000.00
2.2 INTERNAL PAINTING WORKS					
Description / Specification	Mode	Est. Qty	Unit	Rate (₹)	Amount (₹)
2 coats putty + primer + royal emulsion	Calculated	3,500	Sq.ft	35.00	1,22,500.00
Melamine polish on wooden main door	Lump Sum	-	-	-	18,500.00
TOTAL FOR SECTION: INTERIOR FINISHING PACKAGE					Rs. 4,02,000.00

SECTION 3: ELECTRICAL ROUGH-IN & FIXTURES					Group: Electrical & Networking
---	--	--	--	--	--------------------------------

BISMILLAH CONSTRUCTION

Bill of Quantities / Client Quotation

Generated: 31 Jul 2026, 2:30 pm

Period: All Time / Current Snapshot

SECTION 3: ELECTRICAL ROUGH-IN & FIXTURES				Group: Electrical & Networking	
Description / Specification	Mode	Est. Qty	Unit	Rate (₹)	Amount (₹)
FRLS copper wiring throughout villa	Lump Sum	-	-	-	1,50,000.00
TOTAL FOR SECTION: ELECTRICAL ROUGH-IN & FIXTURES				Rs. 1,50,000.00	

QUOTATION ROLLUP SUMMARY BY TRADE GROUP	
TOTAL FOR GROUP: CIVIL	Rs. 7,25,000.00
TOTAL FOR GROUP: FINISHING & SERVICES	Rs. 4,02,000.00
TOTAL FOR GROUP: ELECTRICAL & NETWORKING	Rs. 1,50,000.00
GRAND TOTAL (G-TOTAL)	Rs. 12,77,000.00